Carbon Capture and Usage @Twence

CATO Meets the Projects4 December 2018 Utrecht









Twence®

Introduction


- Vision for CCU
- Carbon Capture and Usage @Twence
- Roadmap from 2008 onwards
- Improved CO₂ Capture (TNO)
- Status of upscaling
- Challenges








Twence vision for CCU





Twence vision for CCU





Carbon Capture and Usage @ Twence



First installation in the world that 'mineralizes' CO₂ for re-use (absorbent) In flue gas scrubbing



Carbon Capture and Usage @Twence



4-12-2018 Utrecht



Twence CCU roadmap from 2008 onwards

Rationale for CO₂ valorisation

to produce sodium-bicarbonate (SBC) to reduce acid gas emissions (CI, SO2) towards zero-emission waste treatment

Reaction

 $Na_2CO_3 + H_2O + CO_2 \rightarrow 2 NaHCO_3$

CO₂ reduction

3,000 tonnes per year

SBC production

8,000 tonnes per year

Roadmap towards demonstration

First idea demo on CO₂ capture

Start 3 kton/a Demonstration Plant

Commissioning

Demonstration Programme

Preparation 100 kton/a Full Scale Plant

CEWEP Innovation Award

Autumn 2007

July 2011

October 2014

2014 onwards and ongoing

2017 onwards and ongoing

20th September 2018 Bilbao





Improved CO2 Capture @ TWENCE

1. Optimization of demo operation

Goals:


- enhance availability
- lower maintenance costs
- 2. Solvent strategy for full scale CO2 Capture at Twence

Goals:

- de-risk the 100 ktonne CCU project
- facilitate the investment decision
- support the application for the environmental permit



Representation of CO2 capture and utilization plant at Twence





5 Work packages

WP1 Troubleshooting pilot operation

WP2 Modifications to pilot

WP3 Improved control

WP4 Full scale derisking

WP5 Management and dissemination





WP1 Results

WP1 Troubleshooting pilot operation


WP2 Modifications to pilot

WP3 Improved control


WP4 Full scale derisking

WP5 Management and dissemination

Evaluation of process data




Process simulation \rightarrow



Diagnosis and recommendations


- Design of plant modifications ready (input data for WP2)
- Opportunity for 30% energy savings identified





WP 2 Modification to demo plant

- Engineering Q4 2018
- Procurement Q1 2019
- Construction Q2 2019
- Testing MEA Q2/3 2019







WP3 results

WP3 Improved control





- TNO's Chemcube installed and operationsl at Twence
- Online monitoring of solvent and CO₂ compositions
- Live diagnosis of plant performance





WP4 Results

WP4 Full scale derisking



Initial results:

Gas composition

- Major components
- Minor impurities
- Particulate materials (PM)

Diagnose:

Low content of impurities and PM → expected low emissions

New solvent test in 2019 with the same monitoring equipment





Next steps

- Complete plant modifications
 - Improved water balance, improved CO₂ throughput
 - Increased flexibility: ready to operate with other solvents
- De-risk full scale project (100kton)
 - Monoethanolamine (MEA) campaign
 - Chemcube → Online solvent and CO₂ monitoring
 - FTIR → Online emissions measurement
 - ELPI → Quantify aerosol emissions (if any)
- Dissemination
 - TCCS-10 (Trondheim, June 2019) planned



Status of Large Scale CCU

Positioning

- WtE line 3
- Dry flue gas cleaning line 3
 - ESP
 - Bag House Filter: activated carbon & sodium bicarbonate injection
 - SCR

Planning

Start operation Q2 2021

Key Decision Making Hold Points

- Environmental Permit
- Grants for Subsidies
- Financial Closure
- Approval of Supervisory Board
- Contracts for off take and design & construction





Feasibility Captured CO₂ to Green houses

- 100 kton CO₂ Capture installation (Tendering procedure)
- Design package
 - Proces development and interfacing
 - Solvent developments and choices
- Market consultation to identify possible bottle necks
 - Dependency on (new) subsidy regulations
 - Future policy and financial instruments for CCU
- Alternative markets for CO₂



Challenges

- Development time 10 years from initial idea towards upscaling
- Learning curve (process stability) requires development time
- Uncertainties in upscaling to a commercial plant

Risk of delay in project realization whilst acceleration is needed!



THANK YOU FOR YOUR ATTENTION

Twence®

Andy Roeloffzen
Project Manager
a.roeloffzen@twence.nl

Ronald de Vries
Manager Projects
r.devries@twence.nl



Juliana Monteiro Research Scientist juliana.monteiro@tno.nl Earl Goetheer
Principal Scientist Process technology
earl.goetheer@tno.nl

